

HA-250 Easement

Form 10-200  
(Rev. 6-72)

UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICE

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Type all entries - complete applicable sections)

STATE:
Maryland
COUNTY:
Harford
FOR NPS USE ONLY
ENTRY DATE

1. NAME	
COMMON	Vestry House, St. George's Parish
AND/OR HISTORIC:	

2. LOCATION			
STREET AND NUMBER: 1522 Perryman Road			
CITY OR TOWN: Perryman		CONGRESSIONAL DISTRICT: First	
STATE Maryland	COOE 24	COUNTY: Harford	COOE 025

3. CLASSIFICATION							
CATEGORY (Check One)		OWNERSHIP		STATUS		ACCESSIBLE TO THE PUBLIC	
<input type="checkbox"/> District	<input type="checkbox"/> Building	<input type="checkbox"/> Public	Public Acquisition: <input type="checkbox"/> In Process <input type="checkbox"/> Being Considered	<input checked="" type="checkbox"/> Occupied	Yes: <input type="checkbox"/> Restricted <input checked="" type="checkbox"/> Unrestricted <input type="checkbox"/> No		
<input type="checkbox"/> Site	<input checked="" type="checkbox"/> Structure	<input checked="" type="checkbox"/> Private		<input type="checkbox"/> Unoccupied			
<input type="checkbox"/> Object	<input type="checkbox"/> Both	<input type="checkbox"/> Being Considered		<input checked="" type="checkbox"/> Preservation work in progress			
PRESENT USE (Check One or More as Appropriate)							
<input type="checkbox"/> Agricultural	<input type="checkbox"/> Government	<input type="checkbox"/> Park	<input type="checkbox"/> Transportation	<input type="checkbox"/> Comments			
<input type="checkbox"/> Commercial	<input type="checkbox"/> Industrial	<input type="checkbox"/> Private Residence	<input type="checkbox"/> Other (Specify)				
<input checked="" type="checkbox"/> Educational	<input type="checkbox"/> Military	<input checked="" type="checkbox"/> Religious					
<input type="checkbox"/> Entertainment	<input type="checkbox"/> Museum	<input type="checkbox"/> Scientific					

4. OWNER OF PROPERTY			
OWNER'S NAME: St. George's Parish			
STREET AND NUMBER: 1522 Perryman Road, P. O. Box 22			
CITY OR TOWN: Perryman		STATE: Maryland	COOE 24

5. LOCATION OF LEGAL DESCRIPTION			
COURTHOUSE, REGISTRY OF DEEDS, ETC: Clerk of the Court of Harford County			
STREET AND NUMBER: 45 South Main Street			
CITY OR TOWN: Bel Air		STATE: Maryland	CODE 24

6. REPRESENTATION IN EXISTING SURVEYS			
TITLE OF SURVEY:			
DATE OF SURVEY: <input type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> County <input type="checkbox"/> Local			
DEPOSITORY FOR SURVEY RECORDS:			
STREET AND NUMBER:			
CITY OR TOWN:		STATE:	CODE

STATE: Maryland	COUNTY: Harford	ENTRY NUMBER	DATE

SEE INSTRUCTIONS

7. DESCRIPTION			
CONDITION	(Check One)		
	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Good	<input type="checkbox"/> Fair
	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
(Check One)		(Check One)	
<input checked="" type="checkbox"/> Altered	<input type="checkbox"/> Unaltered	<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site
DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE			
<p>The original specification for the Vestry House is an excellent description of the present building.</p> <p>'At the Vestry Held for St. George's Parish on Tuesday the 10th Day of June 1766. . . .</p> <p>The Vestry Proceeds to businefs. . . .</p> <p>The Vestry Agrees that there Shall be a New Vestry House built at St. George's Parish Church: According the following Dimentions Viz: To Be Built Twenty foot Long by Sixteen foot wide in the Clear. The foundation to be Sunk Eighteen Inches in the Ground &amp; Rais'd Eighteen Inches above Ground before the Sleepers are Let Down &amp; Sleepers all to be of Good Sound White Oak. Eight Inches Sqare &amp; Between the floor and Cealing Eight foot. The wall to be Two Brick &amp; half Thick to the Sleepers from the Sleepers to the Sqare two Brick Thick The Gave Ends to be one Brick &amp; half Thick to the Square from the Sqare to the Top one Brick Thick. The Work before mention'd to be done with Sufficent Lime Morter &amp; Sand the Roof to have Eighteen Inches over Jet &amp; the Joist to be of good Sound White Oak Seven Inches by four--&amp; Proper Rafters for ye Same &amp; to be Cover'd with Cyprefs Shingles &amp; to Show Six Inches &amp; the Shingles to be Round'd. The Under floor to be of good Quart'd pine Plank one Inch &amp; half Thick. The Cealing to be Lath'd &amp; plaister'd &amp; the Door to be in the South Gave End with Sufficent Lock &amp; Hinges. The house to have a Corner Chimney well Support'd With a half inch &amp; half Quarter Bar of Iron. the Chimney to be four foot wide at the Back &amp; to be properly flier'd &amp; the Jams to be Eighteen Inches Thick: from the floor to the Arch of the Chimney four foot &amp; the Chimney to Extend four foot above the Roof of the House--To be Two Sash Windows on Each Side with Twelve Lights in Each Window the Glafs to be Eight Inches by Ten Wide. &amp; Good Sufficent Window Shutters with Spring Bolts to the Same The whole House to be Plaister'd &amp; White wash'd. the Harth to be Laid with Brick Under the fire place &amp; Round the fire place to be Laid with flag Stone that is now Lay'd in the old Vestry House.</p> <p>The Vestry Adjourns till the 21st day of June by ten oClock'</p> <p>One side--the west--received but one window because the corner fireplace occupyes part of that wall</p> <p>Exterior walls are of Flemish bond, with closers and occasional glazed headers; both gables appear to have been rebuilt, as they are of common bond, but probably of the original bricks. A slate roof has replaced the wooden shingles, and a rake overhang has been added. The unmoulded cornicework is probably of the twentieth century.</p>			

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet) #1

STATE Maryland	
COUNTY Harford	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

NA-256

(Number all entries)

Vestry House, St. George's Parish

7. DESCRIPTION, continued

Rafters appear to date from the late nineteenth or early twentieth century, but the collar beams are original. Ceiling joists are original. The floor structure has been replaced with concrete.

Interior walls are plastered over sawn lathe, applied to furring strips; original plaster and nailing blocks behind the later finish indicates a chair rail at sill height. The original mantel no longer exists and the fireplace has been reduced in size. The door is of vertical beaded boards, with battens attached by wood screws, probably dating from the nineteenth century.

A restoration program is in progress to restore, authentically, missing elements, including the wooden floor, baseboard and chair rail, and mantel surrounding a fireplace restored to its original size. Adequate electric service, and electric heat, will be introduced. A later phase will restore exterior features, including roofing and cornice work, door and door frame, windows and shutters.

St. George's Parish Church, which the Vestry House was built to accompany, was constructed in 1759-1760, and was the third church to occupy this site. The present building, called Spesutia Church, was designed by Niernsee and Neilson, architects in Baltimore, and built in 1851. It is the fourth church on the site. Vestry records indicate that it stands on the foundations of and incorporates bricks from the third church, but it is not known whether or not the present walls, above ground, incorporate standing sections of the eighteenth century walls.

Designed in the Italian Romanesque style, Spesutia Church is of four bays with a chancel at its east end of one bay plus a semi-octagonal apse. In the second bay from the west end, on the south side, is a small entrance porch and at the northwest corner is an external tower of three storeys, the top one being octagonal with louvres on each side; above is a short concave spire.

The buttressed brick walls are stuccoed, scored in imitation of ashlar. A single window in each bay is a tall round headed lancet, filled with small square quarrels set diagonally in wood muntins. Most of the clear glass is original. The three windows of the apse are filled with distinguished contemporary glass designed by Paul Barchowsky, an artist in the parish.

The low-pitched roofs are covered with slate and the generous eave and rake overhangs are supported by wood brackets.

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet) #2

HA-250

STATE Maryland	
COUNTY Harford	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

Vestry House, St. George's Parish

7. DESCRIPTION, continued

The roof trusses are exposed, internally, and the walls are plastered. A large round headed arch separates the chancel from the nave and a gallery, one bay deep, extends across the west end, accessible from a stair within the tower.

Vestry records indicate that the church is on the foundations of, and incorporates bricks from the third church, constructed in 1759-60. Whether the present walls, above ground, incorporate standing sections of the eighteenth century walls is not known. Christ Church, Accokeek in Prince George's County, has had a similar building history; although its style was changed drastically in the nineteenth century, to one not unlike Spesutia, the majority of its walls date from the previous century.

The large cemetery which surrounds Spesutia Church, its colonial Vestry House, and its twentieth century Parish House, was established in 1718, when the Parish's second church was established in the present location. The third church was erected in 1759-60 immediately north of the second, which was then demolished. The fourth or present church was built upon the foundations of the third, in 1851.

The cemetery has many eighteenth century tombstones, and is the largest one of this period in the county. Continuing in use to this day, it has many nineteenth and twentieth century tombstones as well, exhibiting the full range of that art.

Several notable trees are interspersed among the graves, and the entire site is well shaded.

Many eighteenth and nineteenth century stones are known to have been moved to this parish cemetery from private cemeteries, mostly from the nearby Aberdeen Proving Ground and Edgewood Arsenal.

8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)			
<input type="checkbox"/> Pre-Columbian	<input type="checkbox"/> 16th Century	<input checked="" type="checkbox"/> 18th Century	<input type="checkbox"/> 20th Century
<input type="checkbox"/> 15th Century	<input type="checkbox"/> 17th Century	<input type="checkbox"/> 19th Century	
SPECIFIC DATE(S) (If Applicable and Known) <u>1766</u>			
AREAS OF SIGNIFICANCE (Check One or More as Appropriate)			
<input type="checkbox"/> Aboriginal	<input checked="" type="checkbox"/> Education	<input checked="" type="checkbox"/> Political	<input type="checkbox"/> Urban Planning
<input type="checkbox"/> Prehistoric	<input type="checkbox"/> Engineering	<input checked="" type="checkbox"/> Religion/Philosophy	<input type="checkbox"/> Other (Specify) _____
<input type="checkbox"/> Historic	<input type="checkbox"/> Industry	<input type="checkbox"/> Science	_____
<input type="checkbox"/> Agriculture	<input type="checkbox"/> Invention	<input type="checkbox"/> Sculpture	_____
<input checked="" type="checkbox"/> Architecture	<input type="checkbox"/> Landscape Architecture	<input type="checkbox"/> Social/Humanitarian	_____
<input type="checkbox"/> Art	<input type="checkbox"/> Literature	<input type="checkbox"/> Theater	_____
<input type="checkbox"/> Commerce	<input type="checkbox"/> Military	<input type="checkbox"/> Transportation	_____
<input type="checkbox"/> Communications	<input type="checkbox"/> Music		
<input type="checkbox"/> Conservation			

STATEMENT OF SIGNIFICANCE

In colonial Maryland, Church of England parish Vestries usually authorized a special building<sup>1</sup> for use as a meeting place to conduct parish business and to perform certain civil duties (as trustees of the government-supported church), particularly the monitoring of the moral codes of the day and the administering of justice for violations. Vestry Houses were often used as school-houses, school being conducted by the clergyman or a member of his family, of someone else hired by the parish for the purpose. Vestries often replaced their Vestry Houses, as they did their churches, during the colonial period.

With the disestablishment of a state religion at the time of the American Revolution, Vestries no longer officially monitored their community's morals, but they did continue to function as the governing boards of their parishes, and they presumably conducted their meeting in their Vestry Houses. Vestry Houses continued to be used as schools. The Vestry Minutes, from time to time, name schoolmasters who kept school in the St. George's Parish Vestry House, including the years 1812 and 1821. Without governmental support, however, building maintenance became increasingly burdensome, and Vestries probably found it both more convenient and more economical to meet in private residences, and Vestry Houses gradually fell out of use. Only two have survived in Maryland--St George's and that of St. Paul's Parish, Kent County.

Not only is this Vestry House a rare survivor in the state of one type of building, it is a survivor of the eighteenth century, in an area with relatively few eighteenth century structures. As Harford was the last of the tidewater counties to be settled, it had fewer substantial eighteenth century structures than other tidewater counties, hence fewer have been considered good enough through the years to retain. The Vestry House shows that the workmanship and detail incorporated in such a small building was identical to that incorporated into larger, more impressive and more important structures. Finally, that such a small structure has survived without additions is unusual.

SEE INSTRUCTIONS

NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Continuation Sheet) #3

HA-250

STATE Maryland	
COUNTY Harford	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

(Number all entries)

Vestry House, St. George's Parish

8. SIGNIFICANCE, continued

St. George's Parish has long recognized the historical value of their Vestry House, for in 1905<sup>2</sup>, after apparent neglect, extensive repairs were undertaken, but the original character was not substantitally altered. Appreciation for the antiquity of this structure continued, for a restoration program is in progress to restore, authentically, those parts lost or altered from the original.

The Vestry House stands in an extensive cemetery, established in 1718 when Spesutia Church, St. George's Parish, erected its second church there. The present church (the fourth) dates from 1851, designed in the Italian Romanesque style by Niernsee and Neilson, Architects of Baltimore, Maryland. It is on the foundation, and is the exact size, of the third church of 1758; its stuccoed walls are recorded as being constructed of materials from the third church.<sup>3</sup>

Although the chief significance of this property is the rare eighteenth century Vestry House, the architects of the present church J. Craford Neilson (1816-1900) and John R. Niernsee (1831-1885). This team known as Niernsee and Neilson is responsible for major buildings in Baltimore in the 1850's: St. Luke's Church (National Register), Grace and St. Peter's Church, two of the most prominent residences on Mount Vernon Place (National Historic Landmark), Thomas--Jenks--Gladding and Walters Houses, <sup>and</sup> Camden Station. The Spesutia Church provides an exception to the firm's predilection for Gothic in the spirit of the ecclesiologists. (See: Phoebe Stanton. The Gothic Revival in American Church Architecture: An Episode in Taste, (Baltimore: Johns Hopkins Press, 1968).

HA-250

9. MAJOR BIBLIOGRAPHICAL REFERENCES

- 1 Nelson Waite Rightmyer Maryland's Established Church, 1956.
- 2 Vestry Minutes, St. George's Parish
- 3 Ibid

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees	Minutes	Seconds
NW	0     '     "	0     '     "		0		
NE	0     '     "	0     '     "				
SE	0     '     "	0     '     "				
SW	0     '     "	0     '     "				

APPROXIMATE ACREAGE OF NOMINATED PROPERTY: 15 acres

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE

11. FORM PREPARED BY

NAME AND TITLE:		DATE	
<u>James Thomas Wollon, Jr., AIA</u>		<u>July, 1974</u>	
ORGANIZATION			
<u>Harford County Committee, Maryland Historical Trust</u>			
STREET AND NUMBER:			
<u>600 Craigs' Corner Road</u>			
CITY OR TOWN:		STATE	CODE
<u>Havre de Grace</u>		<u>Maryland</u>	<u>24</u>

12. STATE LIAISON OFFICER CERTIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National ☐ State ☐ Local ☐

Name Orlando Ridout IV

Title State Historic Preservation Officer

Date \_\_\_\_\_

NATIONAL REGISTER VERIFICATION

I hereby certify that this property is included in the National Register.

\_\_\_\_\_  
Director, Office of Archeology and Historic Preservation

Date \_\_\_\_\_

ATTEST:

\_\_\_\_\_  
Keeper of The National Register

Date \_\_\_\_\_

SEE INSTRUCTIONS

MD. HISTORICAL TRUST  
BOX 1704  
ANNAPOLIS, MD. 21404NATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Type all entries - complete applicable sections)

1302504208  
N. R. FIELD SHEET

STATE:

HA 250

COUNTY:

FOR NPS USE ONLY

ENTRY NUMBER

DATE

## 1. NAME

COMMON:

Spesutia Vesky

AND/OR HISTORIC:

## 2. LOCATION

STREET AND NUMBER:

Northeast corner of Perryman Road (Md 159) and Spesutia Church Road

CITY OR TOWN:

Perryman

or About 0.8 mi south of Pte 40 on Spesutia Church Road

STATE

Maryland

COOE

COUNTY:

Harpur

COOE

## 3. CLASSIFICATION

CATEGORY  
(Check One)District ☐  
Site ☐Building ☒  
Structure ☐Object ☐Public ☐  
Private ☒Both ☐

OWNERSHIP

Public Acquisition: ☐In Process ☐Being Considered ☐

STATUS

Occupied ☒Unoccupied ☐Preservation work  
in progress ☐ACCESSIBLE  
TO THE PUBLICYes: ☐Restricted ☒Unrestricted ☐No: ☐

PRESENT USE (Check One or More as Appropriate)

Agricultural ☐Government ☐Park ☐Transportation ☐Comments ☐Commercial ☐Industrial ☐Private Residence ☐Other (Specify) ☐Educational ☐Military ☐Religious ☐Entertainment ☐Museum ☐Scientific ☐

## 4. OWNER OF PROPERTY

OWNERS NAME:

Vesky of St. George's Parish

STREET AND NUMBER:

CITY OR TOWN:

Perryman

STATE:

Maryland

COOE

## 5. LOCATION OF LEGAL DESCRIPTION

COURTHOUSE, REGISTRY OF DEEDS, ETC:

CLERK OF THE CIRCUIT COURT

STREET AND NUMBER:

HARFORD COUNTY COURTHOUSE

40 S. MAIN ST.

CITY OR TOWN:

BEL AIR

STATE:

MARYLAND

COOE

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

## 6. REPRESENTATION IN EXISTING SURVEYS

TITLE OF SURVEY:

DATE OF SURVEY:

Federal ☐State ☐County ☐Local ☐

DEPOSITORY FOR SURVEY RECORDS:

STREET AND NUMBER:

CITY OR TOWN:

STATE:

COOE

STATE:

COUNTY:

FOR NPS USE ONLY  
ENTRY NUMBER  
DATE

SEE INSTRUCTIONS



## 7. DESCRIPTION

CONDITION	(Check One)					
	Excellent <input checked="" type="checkbox"/>	Good <input type="checkbox"/>	Fair <input type="checkbox"/>	Deteriorated <input type="checkbox"/>	Ruins <input type="checkbox"/>	Unexposed <input type="checkbox"/>
INTEGRITY	(Check One)			(Check One)		
	Altered <input type="checkbox"/>	Unaltered <input checked="" type="checkbox"/>	Moved <input type="checkbox"/>	Original Site <input checked="" type="checkbox"/>		

DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE

Brick, one story, vesting, one room,  
 two bays by one; facing west, the  
 ridge-lip runs east west, windows 6/6.

SEE INSTRUCTIONS

## SIGNIFICANCE

## PERIOD (Check One or More as Appropriate)

Pre-Columbian ☐16th Century ☐18th Century ☒20th Century ☐15th Century ☐17th Century ☐19th Century ☐

## SPECIFIC DATE(S) (If Applicable and Known)

1766

## AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

Aboriginal ☐Education ☐Political ☐Urban Planning ☐Prehistoric ☐Engineering ☐

Religion/Phi-

Other (Specify) ☐Historic ☐Industry ☐lasaphy ☐Agriculture ☐Invention ☐Science ☐Art ☐Landscape ☐Sculpture ☐Commerce ☐Architecture ☐

Social/Human-

Communications ☐Literature ☐itarian ☐Conservation ☐Military ☐Theater ☐Music ☐Transportation ☐*Architectural*

## STATEMENT OF SIGNIFICANCE (Include Personages, Dates, Events, Etc.)

Built eight years after the third  
 Speculation Church for the St George's  
 Parish, this simple rocky building  
 remains because of its antiquity, its  
 usefulness outmoded.

SEE INSTRUCTIONS

## 9. MAJOR BIBLIOGRAPHICAL REFERENCES

Wright, C. Miller. *Our Harbors Heritage* p 196.

## 10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN ONE ACRE		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE

## 11. FORM PREPARED BY

NAME AND TITLE:

JEAN S. EWING

ORGANIZATION

MARYLAND HISTORIC TRUST

DATE

STREET AND NUMBER:

50 STATE CIRCLE

CITY OR TOWN:

ANNAPOLIS

STATE

MARYLAND

CODE

## 12. STATE LIAISON OFFICER CERTIFICATION

## NATIONAL REGISTER VERIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National ☐ State ☐ Local ☐

Name \_\_\_\_\_

Title \_\_\_\_\_

Date \_\_\_\_\_

I hereby certify that this property is included in the National Register.

\_\_\_\_\_  
Chief, Office of Archeology and Historic Preservation

Date \_\_\_\_\_


ATTEST:

\_\_\_\_\_  
Keeper of The National Register

Date \_\_\_\_\_

SEE INSTRUCTIONS

PERRYMAN QUADRANGLE  
USGS 7.5 minute map  
scale: 1: 24 000  
1948





Vestry House, St. Georges Parish HA-250  
Perryman, MD  
Susan M. Deeney 9/1/76  
East



Vestry House, St. Georges Parish HA-250  
Perryman, MD  
Susan M. Deeney 9/1/76  
Southwest